

BOQ ENGINE REPORT

Project File: 5354e638-ecec-4328-80e0-b3df4de5436b_sample.dxf

Units: m | Scale: 1:100

Sr.	Description	Unit	Qty	Rate	Amount
1	Providing and casting RCC slab M25, 150 mm thick, including formwork, reinforcement placement, compacting, curing and finishing complete. [RCC]	m ²	42.86	■1315.80	■56395.80
2	Constructing brick masonry wall 230 mm thick in cement mortar 1:6 including curing and joints. [Masonry]	m ²	25.73	■220	■5659.50
3	Internal cement plaster 12 mm thick on masonry surface, including preparation, curing and finishing. [Plaster]	m ²	88.4	■148	■13086.32
4	Providing and laying vitrified flooring tiles 600x600 mm with screed, adhesive and grouting complete. [Flooring]	m ²	16.9	■225	■3780.00
5	Supply and installation of flush door 900x2100 mm with frame, hinges, handles and lockset. [Doors & Windows]	nos	1	■320	■320.00
6	Supply and fixing of aluminium glazed window 1500x1200 mm with frame and glass. [Doors & Windows]	nos	1	■240	■240.00
7	Providing and fixing CPVC water supply pipeline 20 mm dia including fittings and support. [Plumbing]	m	27.3	■20	■546.00
8	Providing and fixing electrical light point with conduit and accessories complete. [Electrical]	nos	1	■25	■25.00

Summary

Subtotal: ■27147.30

Tax: ■1357.37

Grand Total: ■28504.67