

# BOQ ENGINE REPORT

Project File: 839c6bf6-c12d-4e7f-ae92-ea75b50aba4c\_sample.dxf

Units: m | Scale: 1:100

| Code    | Category        | Description                              | Qty   | Unit | Rate   | Amount     |
|---------|-----------------|------------------------------------------|-------|------|--------|------------|
| RCC-001 | RCC             | Providing and casting RCC slab M25, 150  | 43.86 | m3   | ■5800  | ■254388.00 |
| MAS-002 | Masonry         | Constructing brick masonry wall 230 mm t | 25.73 | m2   | ■1550  | ■39873.75  |
| PLS-003 | Plaster         | Internal cement plaster 12 mm thick on m | 23.1  | m2   | ■270   | ■6237.00   |
| FLR-004 | Flooring        | Providing and laying vitrified flooring  | 16.8  | m2   | ■1450  | ■24360.00  |
| DOR-005 | Doors & Windows | Supply and installation of flush door 90 | 1     | nos  | ■18500 | ■18500.00  |
| WIN-006 | Doors & Windows | Supply and fixing of aluminium glazed wi | 1     | nos  | ■28000 | ■28000.00  |
| PLM-007 | Plumbing        | Providing and fixing CPVC water supply p | 27.3  | rmt  | ■220   | ■6006.00   |
| ELE-008 | Electrical      | Providing and fixing electrical light po | 1     | nos  | ■1800  | ■1800.00   |

## Summary

Subtotal: ■379164.75

Tax: ■18958.24

Grand Total: ■398122.99